



Echelle en X : 1/2500
Echelle en Y : 1/35

PC : 19.50 m

Altitudes TN	Distances cumulées TN	Pente hydraulique par tronçon	Pente hydraulique générale
22.98	0.00		
23.66	11.59		
23.50	15.31		
22.89	23.12		
22.95	28.75		
23.13	38.86		
23.08	48.51		
22.86	59.04		
23.15	75.58		
23.29	86.71		
23.45	94.18		
23.34	104.57		
23.23	115.51		
23.38	123.70		
23.47	136.69		
23.42	140.93		
23.37	146.93		
23.27	157.04		
23.29	168.94		
23.09	182.89		
23.10	191.90		
23.11	199.38		
23.08	218.56		
23.21	226.57		
23.04	239.20		
23.08	245.61		
22.83	261.20		
23.06	275.60		
22.65	290.59		
22.74	306.22		
22.99	314.03		
22.79	326.95		
22.88	337.45		
22.68	342.83		
23.22	352.87		
23.06	366.08		
23.00	381.69		
22.96	393.93		
22.91	406.89		
22.69	414.00		
22.85	421.57		
22.92	435.10		
22.55	445.11		
22.95	458.01		
22.39	466.87		
22.68	472.34		
22.89	484.06		
23.01	500.35		
22.96	511.13		
22.67	527.41		
22.51	538.77		
22.59	545.37		
22.46	556.58		
22.78	569.31		
22.73	576.30		
22.95	587.74		
22.96	595.23		
22.91	602.72		
22.86	610.21		
22.81	617.70		
22.86	625.19		
22.91	632.68		
22.96	640.17		
22.81	647.66		
22.86	655.15		
22.91	662.64		
22.86	670.13		
22.91	677.62		
22.96	685.11		
22.91	692.60		
22.86	700.09		
22.81	707.58		
22.86	715.07		
22.91	722.56		
21.20	705.59		
21.15	712.56		
21.17	717.45		
20.78	722.48		
20.69	729.49		
21.04	736.77		
20.83	742.66		
20.69	749.49		
20.54	752.00		
20.68	760.44		
21.44	767.77		
19.86	772.80		
20.89	778.89		
20.81	785.17		
20.86	791.77		
20.97	794.17		
21.13	804.93		
21.11	815.24		
21.13	824.56		
20.97	838.21		
21.07	846.95		
21.04	850.08		
21.05	858.90		

Le 06/10/14 (étalage) :
Le 14/04/15 (hautes eaux) :
Le 18/01/15 (crue) :

p = 0.06 %
p = 0.07 %
p = 0.17 %

p = 0.28 %
p = 0.27 %
p = 0.34 %

p = 0.26 %
p = 0.15 %
p = 0.28 %

Rétablissement de la continuité écologique de la Hem
Le moulin Leulienne à Tournehem-sur-la-Hem
Phase : A/VP
Date : 15/07/2015

Maitre d'ouvrage:
Agence de l'Eau Artois Picardie

Maitre d'oeuvre:
Bureau d'études AQUATEC

